

EXPLORE THE POSSIBLE

2 - Safety Non-Negotiables

Whole Current Metering Induction

FM 1202 – Safety Non-Negotiables



Live Works

- Live Work is only permitted when approved by Intellihub and the installer is suitably accredited and authorised
- Unauthorised installers found to be working live will result in disciplinary action which may include removal from the Intellihub project
- All tools must be fit for purpose, inspected, tested and tagged prior to use. Faulty tools and equipment must be made safe and tagged out of service



Risk Management

- Are you fit for work today?
- Onsite risk assessments shall be completed for each job
- Once hazards are identified, take immediate action to eliminate or control the hazard prior to starting work
- If additional hazards are found during works, stop work and reassess controls



Testing Procedure

- Technicians MUST perform all tests as per the work instructions
- Treat all conductors as LIVE until proven otherwise
- All installation connections and polarity SHALL be proven correct by approved methods
- All tests MUST pass successfully. Failure to perform any test could pose a risk to health and safety.



PPE & Test Equipment

- PPE MUST be maintained and worn as per work instructions
- All mandatory PPE must be worn, this applies for all technicians and supervisors
- All test equipment must be maintained and calibrated annually
- Only approved test equipment can be used for testing purposes